BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE
Office of the Executive Engineer, Dasarahalli Division
Schedule-B

NAME OF THE WORK: Engagement of Gangman and Hiring of Tractor Tippers for cleaning and Maintenance of road side drains and other civil works in ward no.12

Sl. No	Description of work	Unit	Qty	Rate quoted by Contractor M/S. Inchara Constructions	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Supply of the 40 HP tractor on daily rate basis to the required place as per the direction of the engineer in charge complete as per the direction of Engineer-in-charge of the work	Day	168.00	1520.00	Rupees One Thousand Five Hundred Twenty Only
2	Supply of the labour heavy mazdoor to the required place as per the direction of the engineer in charge	Day	1344.00	258.88	Rupees Two Hundred Fifty Eight and Eighty Eight Paise Only
3	JCB Excavator complete as per the direction of Engineer-in-charge of the work	Day	30.00	6720.00	Rupees Six Thousand Seven Hundred Twenty Only
4	Tipper complete as per the direction of Engineer-in-charge of the work	Day	20.00	2016.00	Rupees Two Thousand Sixtee Only
	Providing & laying reinforced cement precast slabs of mix CC 1:1 1/2:3 using 20mm & down size graded granite metal using HYSD 10mm dia steel @ 100mm c/c both ways & complete as per specifications (Missed slabs) complete as per the direction of Engineer-in-charge of the work	Sqm	158.40	1600.00	Rupees One Thousand Six Hundred Only

nature of the Contractor

Executive Engineer,
Dasarahalli Division,

Scanned by CamScanner